

Ind 51, 55, 56.

Filed April 2, 1974
1:00 pm


STATE OF WISCONSIN)
) SS
DEPARTMENT OF INDUSTRY,)
LABOR AND HUMAN RELATIONS)

TO ALL TO WHOM THESE PRESENTS SHALL COME, GREETINGS:

I, Stephen J. Reilly, Executive Secretary of the Department of Industry, Labor and Human Relations, and custodian of the official records of said Department, do hereby certify that the attached rules to Wisconsin Administrative Code Chapters Ind 50-59--Building and Heating, Ventilating and Air Conditioning Code, were adopted by the Department of Industry, Labor and Human Relations on April 1, 1974.

I further certify that said copy has been compared by me with the original on file in this Department and that the same is a true copy thereof and of the whole of such original.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the official seal of the Department at the Capitol, in the City of Madison, this 1st day of April, A.D., 1974.


Stephen J. Reilly, Executive Secretary

ORDER OF

DEPARTMENT OF INDUSTRY, LABOR AND HUMAN RELATIONS

Pursuant to authority vested in the Department of Industry, Labor and Human Relations by sections 101.01 to 101.20, Wis. Stats., the Department of Industry, Labor and Human Relations hereby amend, repeals and recreates, and adopts rules of Wisconsin Administrative Code Chapters Ind 50-59-- Building and Heating, Ventilating and Air Conditioning.

The rules attached hereto shall become effective on the first day of the month following publication in the Wisconsin Administrative Code as provided in section 227, Wis. Stats.

Subsection Ind 51.02 (12) (a) to be repealed and recreated to read:

- (a) Parapet walls shall be provided on exterior walls closer than 10 feet to a property line or to other buildings on the same property except as exempted under Ind 51.02 (12) (a) 4. Parapet walls shall satisfy the following requirements:
1. Parapets shall not be less than 2 feet in height.
 2. The minimum thickness of masonry parapets shall be 8 inches.
 3. Parapets shall have fire-resistive ratings as specified for exterior walls in Table 51.03-A.
 4. Parapets are not required on exterior walls which front streets and alleys or where exterior walls connect with roofs of noncombustible construction.

Subsection Ind 51.02 (13) (c) to be amended to read:

- (c) The wall shall connect and make tight contact with roofs of noncombustible construction on both sides of the walls and the roofs shall be noncontinuous at the wall.

Subsection Ind 51.03 (6) (a) to be repealed and recreated to read:

- (a) A building is of metal frame unprotected construction if the enclosing walls are of unprotected metal or unprotected metal in combination with other noncombustible materials and all building elements are as set forth in Table 51.03-A unless otherwise exempted.
1. Heavy timber may be used for interior columns and floor framing.
 2. Interior mezzanines and balconies within the first story may be constructed of one-hour fire-resistive construction.


Subsection Ind 55.02 (2) (a) to be amended to read:

- (a) Not more than one story in height without a balcony, and with no ground floor or basement except a heating and fuel room enclosed with fire-resistive construction as specified in section Ind 55.29, with all interior openings protected with self-closing fire-resistive doors as specified in section Ind 51.047.

Subsection Ind 56.02 (4) (a) 1. to be repealed and recreated to read:

1. Exception. For unlimited capacity, the fire protection of structural steel supporting the roof may be omitted for one-story buildings meeting type No. 1, 2 and 3 construction provided the building has no ground or basement floors. Heavy timber columns and roof framing may be substituted for structural steel framing. The roof decking shall be of noncombustible construction meeting the fire-resistive ratings of Table 51.03-A.

DEPARTMENT OF INDUSTRY, LABOR AND HUMAN RELATIONS



Stephen J. Reilly, Executive Secretary